



One High Tech Avenue, Painesville, OH 44077

Phone: (440) 357-8964 / Fax: (440) 754-8726

[www.evolvetransporters.com](http://www.evolvetransporters.com)

January 14, 2022

Ben Wright  
**Pratt & Miller Racing**  
29600 W.K. Smith Dr.  
New Hudson, MI 48165  
248.278.5133  
[bwright@prattmiller.com](mailto:bwright@prattmiller.com)

## TRAILER PROPOSAL

Quantity	Unit of Measure	Description
----------	-----------------	-------------

### EXTERIOR

1	EA	2023 34" drop frame spread axle trailer body. Constructed of a steel frame, with steel logistic posts, steel roof bows, rounded upper and lower frame rails and a "smooth side" rivetless aluminum skin, 53'L x 13'6"T x 102"W. Includes polished aluminum wheels with stainless hub and lug nut covers, 255 70R 22.5 Michelin tires, and radius aluminum fenders.
1	Trailer	Install custom coach style belly box compartment between axles, primed and painted on curbside only. Roadside to be a split wheel box configuration.
1	EA	Install custom landing gear enclosure with one (1) large exterior access door, hinges up with pneumatic door openers with HD black lockable trigger latches. Constructed of steel tube frame with aluminum skin, bedlined. Compartment will have 12V LED lights with plunger switch on doors.
2	EA	Install large access compartments with painted aluminum doors, stainless steel hinges, and HD black trigger latches. Constructed of tubular steel frame enclosed with aluminum skin. One will be for access to landing gear compartment on the curbside and the other will be for access to floor extension on roadside.
1	EA	Install a 42"W x 76.25"H coach style man door. Design allows for inside or outside operation. Constructed of an aluminum frame with a smooth white aluminum skin.
1	EA	Install an exterior aluminum box step at man door entrance, bedlined black.
1	EA	Install an exterior aluminum box step at rear bedlined black.



- 1 EA Install a 220 volt electric ball screw liftgate with a 5,000 lb. lifting capacity and indoor loading capabilities. Constructed of a steel tube inner structure, smooth .090 aluminum outer skin, 3/16" aluminum plate deck, full width fold out aluminum extension ramp, full steel header, steel outer channels, L.E.D stop, turn and tail lights, all electrical connections and controls.
- 1 EA Install a rear overhead roll-up door.
- 1 EA Install generator housing constructed of a steel tube frame mounted to the front wall of the trailer. Covered with mirror stainless steel skin and doors. Includes a 32 KW, 220 volt single phase diesel generator, auxiliary cooling fan, 70 gallon fuel tank, main and auxiliary batteries, charging system and exhaust scoop. Fully soundproofed with 2" sealed foam.
- 1 EA Install and wire a 220 volt, 100 AMP single phase landline receptacle and matching plug, with 100 AMP transfer switch for generator or power landline, and supply a plug with a 20' cord.
- 1 EA Install a 5 h.p. 220 volt air compressor with a 20 gallon storage tank including all electrical connections, filter, regulator and rough plumbing.
- 4 EA Install a surface mount LED exterior flood light on curbside.
- 24 EA Install and wire a 110-volt GFI, exterior, weatherproof power outlet.
- 4 EA Install an exterior quick disconnect for compressed air, 150 PSI maximum.
- 1 EA Install an exterior coax jack for track side feed located in generator housing.
- 1 EA Install a small custom access door which allows access for liftgate controls. Constructed of an aluminum frame and door with stainless steel hinges and an adjustable trigger latch.
- 3 EA Install 220 volt, 27,000 BTU air conditioner units with a 4,000 watt electric heat strip in the trailer. Includes all necessary duct work for air flow and return air, outside venting, wiring and solid state controls.

**INTERIOR: Upper Deck**

- 47 LF Install insulation between ceiling rafters or roof bows.
- 47 LF Install smooth white aluminum ceiling.
- 851 SF Install white vinyl wall covering between the exposed logistics posts.
- 37 LF Install a fixed deck for car transport. Inner structure made of steel with white aluminum on the bottom and 3/16" natural aluminum on top.
- 188 LF Install (2) rows of e-track cargo tie down painted and installed with e-rope fittings on upper deck and (2) rows on the roadside and curbside walls.

24	EA	Install flush mount LED strip lights in logistics posts and lower wire trough with all wiring and trim in the upper deck.
1	EA	Install and wire the main breaker box with all necessary circuit breakers.
1	EA	Install an aluminum roll-up door from lounge ceiling to deck for climate control.
1	PJ	Install shelving in the upper deck for parts storage. Design and layout is to be determined.

#### INTERIOR: Work Area

9	EA	Install flush mounted LED light strips in an aluminum extrusion with opaque cover. Includes all necessary wiring.
320	SF	Install a black, commercial grade, rubber floor tile.
66	LF	Install (2) rows of recessed black anodized aluminum aircraft track with a black nylon cover and tie down fittings on the floor in the lower deck.
1	EA	Install a rear swing door. Frames will be made of aluminum and powder coated black. Includes full height mirrored windows.
2	EA	Construct and install end panel, constructed of wood with a mirror stainless steel covering.
5	LF	Laminated base storage cabinets with doors constructed of light weight materials, adjustable hinges, trigger latches, and adjustable shelves.
20	LF	Bench tops to have a brushed stainless steel surface and backsplash.
78	SF	Install wood wall covering with a glued mirror stainless steel surface.
32	LF	Laminated upper cabinets with doors constructed of light weight materials, adjustable hinges, trigger latches, and flush mount LED lights.
23	LF	Laminated full height storage/wardrobe cabinets with doors constructed of light weight materials, adjustable hinges, trigger latches, and adjustable shelves.
2	EA	Laminated air conditioner cabinet with upper storage and two adjustable shelves.
1	EA	Install a 110-volt beverage center.
1	EA	Laminated removable steps to the lounge area with commercial rubber tile on the tread surfaces.
1	EA	Install aluminum sliding doors at man door entrance.
1	EA	Install custom removable tubular aluminum ladder from the lower deck to the upper deck, black powder coat finish.
10	EA	Install and wire 110-volt power outlet(s).
6	EA	Install and wire 110-volt power outlet(s) w/USB & USB-C charger.

- 4 EA Install quick disconnect(s) with stainless steel wall plate for compressed air, 150 PSI maximum.
- 15 LF Removable laminated motor box doors (lift off type), constructed of wood and composite with two (2) adjustable trigger latches.
- 1 EA Laminated electrical cabinet with a smoke Lexan door.
- 1 EA Electrical control panel with generator controls, power transfer switch and electrical switches.
- 2 EA Install seats at rear on roadside and curbside of trailer.
- 2 EA Install a 32" TV on roadside wall above seat and one on front wall. Includes HDMI and track feeds.

**INTERIOR: Lounge**

- 1 EA Install a partition wall constructed of steel tube and wood with a laminated swing door, with a magic glass window.
- 15 LF Install sub-ceiling structure of steel tube and natural aluminum top skin.
- 17 LF Cover ceiling with a vinyl headliner available in an assortment of colors.
- 4 EA Install flush mounted LED light strips in an aluminum extrusion with opaque cover. Includes all necessary wiring.
- 294 SF Install wood wall covering with a decorative laminate surface.
- 134 SF Install a commercial grade vinyl plank floor, available in a variety of styles and colors.
- 20 LF Laminated upper cabinets with doors constructed of light weight materials, adjustable hinges, trigger latches, and flush mount LED strip lights.
- 25 LF Install a desk with laminate countertop and backsplash.
- 6 EA Supply and assemble an ergonomic task chair. Includes provisions for securing during transport. The chairs in the expandable room will be attached to the side walls with a swivel base.
- 6 EA Install a high quality 24" LED High Definition monitors located at workstations.
- 1 EA Install a high quality 32" & 43" LED TV on front and back wall of lounge. Tv's to be wired with HDMI and track feeds.
- 1 EA Install a custom fully upholstered leather soft vinyl single seat sofa with base storage drawers
- 6 EA Install and wire 110-volt power outlet(s).
- 6 EA Install and wire 110-volt power outlet(s) w/USB & USB-C charger.

TRAILER & CONVERSION:

**\$696,437**

FEDERAL EXCISE TAX:

**\$31,594**

TOTAL FOR TRAILER:

**\$728,032**

OPTION:

1	EA	Build lounge per layout option #1; Remove slide-out and install a center conference table with upper cabinet and monitor cabinet. Install a sofa on the rear lounge wall. <b>(\$31,024.00)</b>
---	----	---

**PLEASE NOTE:**

- This is an estimate and should not be used for budgeting purposes.
- No state taxes are included in this estimate.
- Price does not include the cost of an awning, exterior paint or graphics.

**CUSTOMER APPROVAL:**

---

Ben Wright  
**Pratt & Miller Racing**

Date